REACTIVEDYNAMICS.JL · STUDY REPORT · GENERATED

Fill-finish capacity for Kestrel and Tern: what to take to ExCo

A ReactiveDynamics.jl study, generated from `agent/studies/launch_supply` and laid out to the six-part report template.

> **Reserve the CMO slot now, usable by either asset, and review at Kestrel's readout: +$3.8M ± $1.1M vs waiting, with a bounded cost in every outcome except both-succeed**

study `agent/studies/launch_supply` **recommended option** `arm_cmo_exit.rdj.json`

generated 2026-09-25 at commit `d007929`

ABOUT THIS REPORT

This report is generated from the study directory `agent/studies/launch_supply` and is laid out to the six-part report template every study follows. It is safe to forward: every figure is embedded, nothing links back into the repository, and nothing in it was written by hand after the study closed. The prose is the study's own briefing, the model section is computed from the model document that produced the numbers, and the provenance section names the commit and the runs.

Slot	Status	Source

1 · Headline: number and verdict	present	FINDINGS.md, first section
2 · Decision rule, caveats as scope	present	FINDINGS.md, 5 section(s)
3 · Why a spreadsheet cannot produce this	present	FINDINGS.md
4 · The model: elements, units, the arm diff	present	generated from `arm_cmo_exit.rdj.json` and BRIEF.md's slot table
5 · Hero visual: the execution map	present	`agent/studies/launch_supply/figures/exec_map_reserve_review_both_s1.svg`
6 · How we got it, and provenance	present	FINDINGS.md, plus generated from the repository and `runs/`

> The REPORT artifact (phase 4 of 4), final revision (turn 9). The recommendation comes first, then the numbers, then how they were computed. **Read this before any number below.** Each figure comes from single simulated paths, one per seed, with the readout outcomes forced. Paired paths per outcome: both succeed 37 (seeds 1–37); Tern only 30 (seeds 1–30, for the recommended rule); Kestrel only and both fail 3 each; the two build options 8 in the both-succeed outcome. The same seed gives every option the same readout dates, slips and lead times. The four outcomes are combined using the stated odds (Kestrel 0.60, Tern 0.45, independent: 0.27 / 0.33 / 0.18 / 0.22). The ± figures are standard errors across paths, and the probability ranges are 95% Wilson intervals on the path counts. The relayed 96-seed ensemble of the wait option serves as an independent check.

1 · THE ANSWER AND THE DECISION RULE

Recommendation: sign the reservation before 30 November 2026, usable for either asset. At Kestrel's readout (March 2027), if Kestrel has failed, move Tern's PPQ in-house, file Tern on our own line, give the CMO notice and pay the forfeit. If Kestrel has succeeded, keep the reservation. Do not build a second line. Do not use the Tern-only structure unless the second CMO contract is in writing.

The wording the user will take to ExCo:

> We recommend reserving the CMO fill-finish slot now, before 30 November 2026, usable by either Kestrel or Tern, and reviewing it at Kestrel's readout in March 2027. If Kestrel fails, Tern's validation batches move to our own line, Tern files there, and we give the CMO notice and pay the forfeit. If Kestrel succeeds, the reservation stands. Modelled over paired simulated paths, this is worth about +$3.8M (±$1.1M) against waiting at the stated odds, and about +$25M if a batch earns its peak-year value. At a 50% chance of Kestrel succeeding it is roughly break-even, around +$1.6M. Its purpose is supply protection. If both products succeed (27% chance at the stated odds), it is worth about +$39M and prevents a Tern launch shortfall that otherwise occurs on 26 of 37 paths, costing on average about 11 batches and $51M. If either product fails, the cost is a bounded $9–11M. We do not recommend building a second line. Even when both products succeed, it is $73–105M worse than waiting if built now and $82–87M worse if built after the readouts (8 paths each). We do not recommend a Tern-only reservation unless the second CMO contract is in writing. The one remaining risk is the CMO qualifying late: if both succeed, Tern's filing can be delayed, and 3 of 37 paths lose money, the worst about $14M.

- **Money is positive and passes the brief's test.** Against waiting: **+$3.8M ± $1.1M**, plausible range +$1.6M to +$6.0M, so $\Delta - 2 \cdot se > 0$. The value sits in the both-succeed world. Every other world is a near-fixed cost, measured at $8.8M–9.7M. The ExCo wording says $9–11M, a conservative bound; see Caveats.


Outcome	Chance	Reserve now + review vs wait	Paths
Both succeed	0.27	+$38.7M ± $4.1M	37

Kestrel only	0.33	–$8.8M ± $0.07M	3
Tern only	0.18	–$9.4M ± $0.02M (range –$9.7M to –$9.3M)	30
Both fail	0.22	–$9.4M ± $0.00M	3

- **The review rule removes the Tern-only tail.**
- Without the rule, reserving lost $31.7M ± $6.0M in the Tern-only world over 10 paths. Four of the 10 fell below –$20M, the worst lost $72.1M, and 4 of 10 filed late.
- With the rule, the loss is all fee and forfeit. Tern's revenue matches waiting on all 30 paths, 0 of 30 file late, and 0 of 30 lose demand.
- The rule never fires when Kestrel succeeds. Checked: it gives the same result as plain reserve-now in the both-succeed and Kestrel-only worlds.
- **What it buys.** If both succeed and we wait, Tern is short at launch on **26 of 37 paths**, which is **0.19 overall (0.15–0.22)**. With the reservation it is short on **0 of 37**.
- **What it does not buy: an on-time Tern filing.** When both succeed, Tern files late on 14 of 37 paths with the reservation (1–3 months) and on 13 of 37 under wait (2–3 months). Overall, the chance of a late Tern filing is 0.102 with reservation and review, and 0.095 without.
- **Kestrel is never short at launch** under either option (0 of 37 paths).
- **The remaining downside is a late CMO qualification.** 3 of 37 both-succeed paths lose money (–$14.3M, –$3.7M, –$5.5M). In each, Tern reads out before the CMO has qualified, and the CMO is Tern's only filed site.
- **Two confirmations the user holds.** Legal confirms that the slot can be reassigned; regulatory confirms that Tern can be filed on our line if Kestrel fails. Both are assumed by the model. If either reverses, the recommendation must be re-run.

Reserve the CMO now, review at Kestrel's readout: eNPV against waiting

Paired single paths (same seed, same dates in both options), whiskers ±1 se (dark) and ±2 se (grey) across paths. Top two bars: odds-weighted overall. Others: given the outcome. Kestrel 60%, Tern 45%, 9% WACC, year-1 value per batch.



Options against waiting

2 · WHAT EACH OPTION COSTS AND PROTECTS AGAINST

eNPV is in $M, at 9% WACC through end-2032, at the year-1 value per batch.

Option	vs wait, overall	vs wait, if both succeed	Tern short at launch, if both succeed	Tern files late, if both succeed	Kestrel short at launch
Wait	—	—	26/37	13/37 (2–3 months)	0/37
Reserve now + review at Kestrel readout	**+3.8 ± 1.1**	**+38.7 ± 4.1**	**0/37**	14/37 (1–3 months)	0/37
Reserve now, no review	−0.2 ± 1.5 (Tern only on 10 paths)	+38.7 ± 4.1	0/37	14/37	0/37

Build after readouts	–23.0 (3 paths, turn 6)	–84.3 ± 0.6; range –86.8 to –82.3 (8 paths)	6/8	—	0
Build now	–105.8 (3 paths, turn 6)	–86.9 ± 3.1; range –104.7 to –72.8 (8 paths)	6/8	—	0

What a Tern shortfall costs. When both succeed and we wait, Tern loses demand on 37 of 37 paths: on average 10.7 batches, worth $50.9M PV (range 5.9–20.3 batches, $27.8M–95.9M), over 5 to 10 months just after launch. With the reservation Tern loses no demand on any of the 37.

Kestrel. Under wait, Kestrel runs slightly short later in its life on 4 of 37 both-succeed paths (0.5 to 3.7 batches, never in its first six months). With the reservation, 0 of 37.

2 · SENSITIVITIES

On the same paired paths, with the review rule:

Case	Reserve now + review vs wait, overall	If both succeed
Base	+$3.8M ± $1.1M (+$1.6M to +$6.0M)	+$38.7M ± $4.1M
Value per batch at the peak rate	+$25.0M ± $2.8M (+$19.3M to +$30.7M)	+$117.3M ± $10.5M, negative on 1 of 37
Kestrel PoS 0.50 (the user's own estimate)	+$1.6M ± $0.9M (–$0.2M to +$3.4M): roughly break-even, narrowly fails the test	+$38.7M ± $4.1M

At the peak rate, the Tern-only loss without review would be –$51.5M on average (worst –$157.0M over 10 paths). With review it stays at –$9.4M. When both succeed, the build options stay negative even at the peak rate: –$88.7M and –$85.0M over 8 paths.

Still on 3 paths from turn 6, indicative only, without the review rule:

- No second CMO contract: reserve-for-both +$16.3M, reserve-for-Tern-only –$72.5M. Deferred at the user's direction, because the Tern-only structure is off the table without

a written contract.

- Literal allocation rule: +$8.8M.
- A $5M walk-away: about +$1.0M.
- Even capex phasing: $0.95M worse.
- The 2-month Kestrel floor: no change.

2 · CROSS-CHECK AGAINST THE 96-SEED WAIT ENSEMBLE: RESOLVED

- **Replays match exactly.** Ensemble members 20, 96 and 6 were replayed with their exact seeds, both unforced and forced to both-succeed. The two versions match each other byte for byte and reproduce the ensemble's late-filing months (2, 2, 0) and lost Tern demand (92, 59, 91 tenths).
- **The eNPV offset is harmless.** eNPV differs by a constant factor of 1.0072 = 1.09^(1/12), a one-month discounting-offset convention that cancels in every comparison.
- **The late-filing gap is sampling chance.** Among the ensemble's 20 both-succeed members, 2 filed late (2 months each); our paths show 13 of 37. Fisher exact two-sided p = 0.059: chance, not a model or forcing error.
- **Pooled late filing:** 15 of 57 (0.26, range 0.17–0.39).
- **Pooled Tern short at launch:** 40 of 57 (0.70), which is 0.19 overall (0.155–0.217), in line with our 0.19.
- **Scope:** the other turn-7 checks agreed (eNPV, P(Tern short), P(Kestrel short), Tern demand lost). The late-filing figures remain the least precise in this report. The ensemble covers only the wait option.

2 · WHAT WOULD CHANGE THE ANSWER

- **Kestrel's odds.** At PoS 0.50, which is the user's own estimate, the result is roughly break-even: +$1.6M ± $0.9M.
- **The value per batch.** At the peak rate the case is strong: +$25.0M.

- **Legal or regulatory reversing.** Either reassignment of the slot or filing Tern on our own line after a Kestrel failure. The review rule depends on the latter.
- **Whether a second CMO contract really exists.** It separates reserve-for-both from reserve-for-Tern-only.
- **A backup Tern qualification on our own line when both succeed.** This would address the remaining downside (3 of 37 paths). Not modelled, at the user's direction.

2 · CAVEATS

- **Horizon.** The model ends in 2032, so value earned after 2032 is not counted; the build options are understated as a result.
- **Validation cost, and a correction.** Revision 3 said the Tern-only cost was understated by about $1M because own-line PPQ is charged at $0.15M/batch rather than regulatory's $0.5M/batch. That overstated the gap. The Tern-only difference against waiting is all CMO fee plus forfeit (cost –$9.40M, Tern revenue +$0.00M). Under both wait and review, the own line is Tern's only filed site. So a higher own-line PPQ cost falls on both options and largely cancels. The $0.5M/batch applies to qualifying a backup site as well, which is not modelled. The ExCo wording's "$9–11M" is a conservative bound on the measured $8.8M–9.7M.
- **Small samples.** The Kestrel-only and both-fail worlds rest on 3 paths each. Their spread is under $0.1M, because the cost there is fee and forfeit.
- **Unverified inputs.** Two remain without paperwork: the second contract and +5%/yr marketed growth. Reassignment of the slot is now confirmed by legal, per the user.
- **Kestrel's share-loss penalty.** The 15% penalty never triggered.

3 · WHY A SPREADSHEET CANNOT PRODUCE THIS

The reservation's value exists only in the joint outcome where both succeed. There it depends on a race between Tern's readout date and two other timelines: the CMO's qualification lead time, and Kestrel's six-month stock build on the same own line. The

review rule works because Kestrel reads out nine months before Tern. It turns a commitment whose worst case depended on that race into one whose worst case is a known fee plus forfeit. Both effects come from month-by-month allocation under drawn dates, not from any per-asset expected value.

<details>
<summary>The model (click to expand)</summary>

The model is monthly, from 1 October 2026 to end-2032, with capacity counted in tenths of a batch. It includes the own line, the reserved CMO slot, a second CMO contract if both succeed, a possible second line, the readout draws, the regulatory clock including PAS, and the patient-first planner. It consists of 23 JSON documents from `gen_models.py` plus forced-outcome copies in `scenarios/`. Each option differs from waiting in one or two parameters. The recommended option is `arm_cmo_exit` (`cmo_now` = 1, `exit_at_k` = 1). Its rule `cmo_exit_k` fires once at Kestrel's readout if Kestrel failed. It releases the CMO slot and CMO PPQ, returns Tern to own-line PPQ and filing, and charges the forfeit.
</details>

4 · THE MODEL

The model is data: a document in the engine's closed vocabulary, checked by a validator before it runs, with no code in it. What follows is computed from `arm_cmo_exit.rdj.json`, the recommended option, so it describes the model that produced the numbers above.

What	In this model
Horizon and tick	`tspan = 75`, `dt = 1`
Places	48: 4 are pools a transition holds and returns (`cmo`, `cmo2`, `line`, `line2`); 3 carry a cost or reward into the ledger (`cash`, `k_sold`, `t_sold`)
Transitions	31: 14 take time (cycle time > 0), 13 can fail (success probability < 1), **12 have a rate that reads the state** (`cmo2_fee`, `cmo_fee`, `k_clock`, `k_demand`, `l2_capex_even`, `l2_capex_y1` +6)

Decision rules	**27**, 26 firing once and 1 every tick; 18 decide on the live state, 1 draw a random input
Parameters	58, every one a named value an arm can change

The elements in the language of the business

The table the study was framed in (BRIEF.md), signed off before the model was built: each slot in the operator's words, and the formal element it became.

Time origin t = 0 is 1 October 2026; one tick = one month; horizon t = 75 (end 2032). All money $M, all capacity batches (the model counts in tenths of a batch internally so fractional monthly rates are exact to 0.1 batch).

Slot	Value (source: user)	Object-model target
Scarce resource	In-house line, effective 12.8 batches/month (nominal 16; ~13 after changeovers and shutdowns; trailing 12 months 12.8). Reusable: a batch occupies the line for its month and gives it back	plain place `line`, `init = 128` (tenths), held `conserved`, 10 units per batch, `cycletime = 1`
Second resource (option 1)	CMO slot, up to 4 batches/month, usable 12–15 months after signing (CMO says 12, experience says 15)	place `cmo` (40 tenths) created at `sign + U(12,15)` by a rule; `conserved` like the line
Third resource (option 2)	Second in-house line, commercial-ready 30–36 months after approval (earliest ~Q2 2029). 12 batches/month effective (turn 4)	place `line2` (120 tenths) created at `approve + U(30,36)`
Background load	Marketed products ~9 batches/month today, +5%/yr (S&OP estimate — soft), never bumped	transition `mkt`, integer monthly count from the cumulative curve `9·1.05^(t/12)/0.97` (grossed up for rejects), taken off the line first
Rejects	~3% of batches rejected	`prob_of_success = 0.97` on every batch transition
Readouts	Kestrel PoS 0.60 (portfolio committee; user thinks generous →	params drawn once at t = 0 by rules (`Bernoulli`, `Uniform`) so every arm sees the same readout

	test 0.50), readout ~March 2027 slipping 0–2 months; Tern PoS 0.45, readout ~Dec 2027 ± 3 months (event-driven). Independent	outcomes and dates per seed
Regulatory clock	Readout → +3 months BLA filing → +12 months standard review (no priority review) → +1 month launch. Filed fill site must have 3 PPQ batches before filing; otherwise the site is added by PAS (~6 months) after approval and cannot ship until approved	rules keyed on the drawn readout time; per-asset per-site "approved to ship" flags
Kestrel's filed site	Own line, PPQ planned Q1 2027	Kestrel may ship from `line` from launch; from `cmo` / `line2` only after a PAS
Tern's filed site	None locked in. Without the CMO, Tern's 3 PPQ batches run on the own line between readout and filing, competing for the same batches as Kestrel's stock build	transition `tern_ppq_own` (3 batches, priority below Kestrel); filing waits until PPQ is done
Launch stock	Six months of forward demand on the shelf at launch: Kestrel ≈12 batches, Tern ≈9–10, built in the six months before launch	stock target = 6 × demand(month + 6), production starts 6 months before launch
Demand (batches/month)	Kestrel 1 at launch → 3 at month 12 (linear) → 4.5 at peak ~year 3 (±30%). Tern 1 → 2.5 at month 12 → 4 at peak ~year 3 (less certain)	`min(1 + a/6, 3 + (a−12)/16, 4.5)` and `min(1 + a/8, 2.5 + (a−12)/16, 4)`, a = months since launch
Contention rule	Marketed first, then Kestrel, then Tern, on every line; Tern PPQ on the own line competes with Kestrel (turn 3)	a `planner` rule at the end of each month allocates next month's free capacity in tiers — Kestrel, Tern PPQ, Tern stock, (Kestrel buffer top-up when `k_first = 0`) — each tier filled own line → line 2 → CMO (cheapest first). Turn 5 correction, base case `k_first = 0`: "the priority was about supplying patients" — Kestrel's launch build and each month's demand first, then Tern's PPQ and

		stock, then Kestrel's buffer top-up; the literal rule (`k_first = 1`, Kestrel's full six-month buffer before any Tern batch) is shown as a sensitivity. Guardrail in both: Kestrel never below 2 months of forward stock (`k_floor = 2`; checked against `k_floor = 0`)
Shortfall cost	Kestrel: short in first six months ⇒ 15% of peak share lost for good (competitor launches 6–9 months after our approval). Tern: shortfall is lost sales only. Unmet monthly demand is lost, not backlogged (turn 4: no delayed variant)	rule sets `k_share = 0.85` once if any Kestrel demand goes unmet with a < 6; unmet orders drain to a `*_lost` tally
Value of a batch sold	Kestrel peak $1.2B/yr, first 12 months $250M; Tern peak $0.9B/yr, first 12 months $150M; margin 85%. Base case: year-1 rate ($10.9M/batch Kestrel, $7.4M Tern, before margin); upside sensitivity: peak rate ($22.2M, $18.8M) — turn 4: "if the recommendation only holds at the peak rate, I need to know that"	`reward` per tenth-batch shipped on `k_sold` / `t_sold`
Costs	CMO: $5M/yr paid annually in advance, 3-year minimum, +$0.4M per batch filled; terminate on 12 months' notice forfeiting that year's fee (walk-away after a failed readout: $10M base = two annual fees, $5M sensitivity = the number quoted in the room, turn 4). In-house: $0.15M/batch. Second line: $120M capex (Class 4, $100–140M), phased 20/50/30 over three years from approval (evenly spread as a sensitivity, turn 4), $10M/yr fixed once operating	`cost` on a deep `cash` pool drawn by fee/capex/batch transitions

Reassigning the CMO slot	Term sheet reserves capacity, not a product — the user's reading, not confirmed. If Tern fails, Kestrel can move in via PAS (CMO won't be ready before Kestrel files)	tested both ways: `arm_cmo` (reassign allowed) and `arm_cmo_tern_only`
Second CMO contract	Turn 5: if both assets succeed, sign a second contract the same week on the same terms ($5M/yr, 3-year minimum, $0.4M/batch, 12–15 months to ready) — the user's estimate, no term sheet. Assumed not to open before mid-2028 like the first	place `cmo2` (40 tenths), signed at max(Tern readout, t = 20) to start the next month, ready after its own `U(12,15)` draw; both assets reach it by PAS. `second_cmo = 0` sensitivity
Horizon and tick	Through end-2032, monthly	`meta.tspan = 75.0`, `meta.dt = 1.0`
Headline metrics	eNPV at 9% WACC ($M); P(supply-constrained launch) per asset	`enpv --annual=0.09 --periods-per-year=12`; `final:k_short`, `final:t_short` (0/1 per path; turn 6: odds-weighted over forced-world paths, see Analysis plan)

Every element

The reviewer's table: each place, transition and rule in the formal vocabulary, with what it reads and what it writes. It is folded in the HTML version and left out of print, where its 106 rows would outweigh the report.

What the option changes

The recommended option is the base model with the lines below changed — that diff *is* the lever. Open it to see it whole.

▸ `MODEL` **`arm_cmo_exit.rdj.json` against `model.rdj.json`** 48 places · 31 transitions · 78 arcs · 27 rules


the whole difference from `model.rdj.json`

```
--- model.rdj.json
+++ arm_cmo_exit.rdj.json
@@ -88,7 +88,7 @@
```

```
    },
    {
     "name": "cmo_now",
-    "value": 0.0
+    "value": 1.0
    },
    {
     "name": "cmo_reassign",
@@ -128,7 +128,7 @@
    },
    {
     "name": "exit_at_k",
-    "value": 0.0
+    "value": 1.0
    },
    {
     "name": "cmo_exited",
```

5 · HERO VISUAL: THE EXECUTION MAP

The network of the recommended option after one run (seed 1): places are pools and states, boxes are transitions, and a highlighted place is one that ran dry at some point — where the contention was. Drawn by `rdx draw scenarios/arm_cmo_exit__both.rdj.json --exec-map --seed=1`.



6 · HOW THE NUMBERS WERE MADE

1. **Frame**: `BRIEF.md`.
2. **Author**: `gen_models.py`. All documents pass validation.
3. **Diagnose**: `DOCTOR.md`. `arm_cmo_exit` diagnoses 7 · 1 · 1, identical to `arm_cmo`.
4. **Report**: single-seed `rdx run` paths, every one `ok`, plus 6 ensemble-seed replays. The command, output excerpt and exit code for each are in `capture_log.md`, turns 6–9. The figure is `figures/options_vs_wait.json`, rendered by `agent/scripts/chartkit.jl`.

The headline numbers come from:

```
(cd agent/studies/launch_supply && python3 exit_review.py)            # recommended
rule, base case
(cd agent/studies/launch_supply && python3 exit_review.py --peak)     # peak value per
batch
(cd agent/studies/launch_supply && python3 exit_review.py --pk=0.5)   # Kestrel PoS 0.50
(cd agent/studies/launch_supply && python3 paired_both.py)            # both-succeed
detail, build options
(cd agent/studies/launch_supply && python3 ens_check.py)              # ensemble cross-
check
```

Each path is determined by (document, seed), and the verbatim outputs are in `runs/` and `runs_ens/`.

Provenance

Repository commit	`d007929`
Study last changed	`d007929 2026-09-25`
Report generated	2026-09-25, by `agent/scripts/render_report.jl`
Engine	ReactiveDynamics.jl 0.3.0
`agent/studies/launch_supply/model.rdj.json`	sha256 `be3d9e138037…`
`agent/studies/launch_supply/arm_cmo_exit.rdj.json`	sha256 `e938410eba08…`

The replay rule. A run is determined by its document and its seed: the same pair gives the same output, bit for bit, on any machine. To check a number, run the document

named above with the seed in the table below and compare against the stored run.

208 stored single-seed runs, each the verbatim JSON output of one `rdx run`:

Document	Paths	Scenario: seeds
`arm_build_after`	11	both: 1–8 · konly: 1 · neither: 1 · tonly: 1
`arm_build_now`	11	both: 1–8 · konly: 1 · neither: 1 · tonly: 1
`arm_cmo`	53	both: 1–37 · konly: 1–3 · neither: 1–3 · tonly: 1–10
`arm_cmo_exit`	33	both: 1 · konly: 1 · neither: 1 · tonly: 1–30
`arm_cmo_literal`	4	both: 1–3 · konly: 1
`arm_cmo_no2`	3	both: 1–3
`arm_cmo_tern_only`	6	both: 1–3 · konly: 1 · neither: 1 · tonly: 1
`arm_cmo_tern_only_literal`	4	both: 1–3 · konly: 1
`arm_cmo_tern_only_no2`	3	both: 1–3
`model`	73	both: 1–37 · konly: 1–3 · neither: 1–3 · tonly: 1–30
`model_literal`	4	both: 1–3 · konly: 1
`model_no2`	3	both: 1–3

Plus 6 stored run file(s) outside the naming convention.

Regenerate this report from the study as it stands:

```
julia --project=. agent/scripts/render_report.jl agent/studies/launch_supply --
arm=arm_cmo_exit.rdj.json --exec-map=figures/exec_map_reserve_review_both_s1.svg --exec-
map-from=scenarios/arm_cmo_exit__both.rdj.json
```

Generated by `agent/scripts/render_report.jl` from the files of the study; edit the study, not this page, and regenerate. The template is the one in `agent/skills/rd-report/SKILL.md`.